

TUMKUR DIVISION.

Dated 18th December 1919.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 12th January 1920, for improving and extending the A.-V. School at Tiptur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A.M., and 5 P.M., on all days except on Sundays and General Holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees (200) two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving and extending the A.-V. School at Tiptur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned on surrendering the receipt granted therefor.

Abstract estimate of quantities for improving and extending the A.-V. School at Tiptur.

Item No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	79
2	Burnt stone in clay	C. ft.	2,966
3	Burnt brick in chunam	"	559
4	Burnt brick in clay	"	2,394
5	Arch work	"	86
6	Cut stone pillars with base and capitals	Each	16
7	Burnt stone slabs dressed	S. ft.	463
8	Chunam plastering	Sq.	44.90
9	White and colourwashing	"	44.90
10	Chunam pointing	"	2.65
11	Teakwood work wrought and put up with wood oiling	C. ft.	180.5
12	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	26.60
13	Ridge tiles set in mortar	R. ft.	99
14	Cornice 9" thick	"	453
15	Zinc sheet for the valley with teak plank underneath	S. ft.	144
16	Teakwood panelling doors (outer dimension)	"	180
17	Teakwood windows outside panelled and inside glazed with iron bars, etc., complete.	"	216
18	Painting silicate	Sq.	10.36
19	Masonry finials	Each	2
20	Teakwood sun shades	"	8
21	Dismantling walls and fixing windows	"	4
22	Removing windows marked "A" in the hall and fixing new doors	"	2
23	Teak cave board 9" wide with wood oiling	R. ft.	140
24	Teak finials	Each	2
25	Teak terminals	"	4
26	Parapet wall	R. ft.	44
27	Flooring with 9" Mangalore tiles or Cuddappah slabs over 3" concrete and cement pointing.	Sq.	15.60
28	Dismantling and removing porch	Each	2
29	Unforeseen jobs found necessary during execution	Lump sum	
30	Clearing site and levelling ground around the school	Do	
31	Gravelling road around the school 7 yards wide	C. yd.	70

B. C. SRINIVAS IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Dated 15th December 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th January 1920, for constructing a bridge of 5 arches of 30 feet span across the halla near Kuparvalli village at 8—7 mile on Nanjangud-T-Narsipur road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.